

History of Freedom Sanitary District No. 1 Wastewater Treatment Plant

Original wastewater treatment plant (WWTP) placed into service in 1973

Major facility upgrades in 1982 and 1997

Most current equipment and processes installed in 1997

Current WWTP Service Parameters:

Service Population: 3,448 people

Average wastewater flow: 0.261 MGD (261,000 gallons/day) Includes 40,000 gallons/day from septage waste haulers



WWTP Upgrade Overview

Planning for WWTP upgrades began in April 2017

Project Scope:

- Evaluate existing facility equipment and wastewater treatment processes
 - What equipment can continue to be used and what must be replaced?
- Evaluate future residential and industrial growth for Freedom Sanitary District No. 1 and develop 20-year projections
- Assess long-term needs
- Develop plan for economic, practical, and reliable future wastewater treatment service for the Sanitary District
- Present economical plan to Sanitary District for WWTP upgrades
- Proceed with design and construction of WWTP upgrades

Cedar

redor

Why are WWTP Upgrades Needed?

The Sanitary District must be able ensure adequate wastewater treatment for at least the next 20 years.

- Avg. flows projected to increase from 0.261 to 0.315 MGD

 Service population projected to increase from 3,448 to 4,228 by 2036
- Additional organic and chemical constituents in wastewater (More wastewater in future and it will be stronger)

Adequate wastewater treatment will be provided by completing the following tasks:

- Proactive replacement of equipment near the end of its service life
- Improve processing quality of septage receiving facilities.
- Add equipment for supplemental solids and grit treatment.
- Incorporate modern technology and tools into the day-to-day operations of the Sanitary District.

WWTP Upgrade Project Phases

Phase I (2018-2019)

Upgrade Septage Receiving Facilities

Replace blowers used for providing air for wastewater treatment

Replace pumps used for handling of sludge

Replace mechanical components on clarifiers

Implement modern-day control and electrical upgrades

Minor site modifications

Phase II (When Needed)

Headworks modifications

Increase aeration capacity of WWTP

Increase sludge storage capacity of WWTP



Phase I Project Schedule

Engineering Planning Report - March 2018

Project Public Hearing – June 2018


Complete Plans & Specifications – June 2018

Project Bidding – August 2018

Begin Project Construction – September 2018

Complete Project Construction – October 2019





Description of WWTP Upgrades

Construction of one new building

Septage Receiving Station (location shown on map)


Mechanical Equipment Replacement


- Blowers to supply air for wastewater treatment
- New pumps for treatment operations
- Repair of existing clarifier units


Utility and Control Software Improvements (SCADA)


























Phase I Project Cost and Sewer User Impacts

Budgeted Project Cost: \$4,000,000 (\$4 million)

Project to be funded by DNR Clean Water Fund (CWF)

No anticipated initial impact on existing sewer user charge rates

Due to recent repayment of existing CWF debt for 1997 construction project Itemized Cost Breakdown:

Septage Receiving Station: \$985,100

Five Aeration Blowers: \$413,500

Sludge Handling Pumps: \$472,300

Clarifier Equipment & Misc. Site Work: \$252,100

Electrical & SCADA: \$1,875,800

Total: \$4,000,000

